

~~SECRET~~

25X1A6a

MODIFICATIONS TO [REDACTED]

25X1A6d

1. Increase the interior and exterior light level to the minimum required by CCTV Security equipment.
2. Cover all openings required for ventilation with the equivalent of a 9 guage expanded metal grill.
3. The roof and siding panels shall be secured such that they cannot be removed from the outside without noticeable damage. (carriage bolts may be one acceptable method)
4. Remove the existing double sliding doors at both ends of the building or secure same in the open position.
5. Fill the double door openings with materials similar to the siding and install a standard hollow metal door at the North end of the building and a double hollow metal door at the South end of the building.
6. Install door contact alarms on each door and connect to an annunciator in the guard office at the main gate.
7. Install "Detex" clock stations at both the North and South end of the building.
8. Install asphalt tile flooring.
9. Install required ventilation equipment (exhaust fan, etc.) to maintain a reasonable maximum temperature in the summer. (see Note 3) Air conditioning and humidity control is not required.
10. Relocate the unit heaters if required.
11. Install CCTV cameras on the exterior of the building to cover all four walls and the roof. Cameras should be as close to the building as possible.
12. Install CCTV cameras on the interior of the building. Locations on each camera will be provided at a later date.
13. Install T.V. monitors in the guard office and connect to cameras listed in Notes 11 and 12.

~~SECRET~~

~~SECRET~~

Approved For Release 2001/08/08 : CIA-RDP74-00005R000100120084-9

25X1C4a NOTE - All CCTV cameras and monitors will be procured by the [REDACTED] (or the contractor). The nomenclature for the CCTV equipment will be provided at a later date.

14. Procure and install shelving as required, shelving shall not be installed against the wall (see proposed arrangement attached). [REDACTED]
14 shelves high.

25X1A

~~SECRET~~